

Project : Proposed Construction of One-Storey Residential Building

Location :

Owner :

Item	Description	Unit	Qty.	Unit Cost	Total Cost
1.0	Permits and Professional Fees				
	Professional Fees/Asbuilt plans	lot	1.00		
	Building Permits	lot	1.00		
	Total Permits and Professional Fees				
2.0	Site Works				
	Cleaning and Site Preparations	lot	1.00		85,000.00
	Backfill and Compaction	cu.m	1.00		130,000.00
	Total Site Works				₱215,000.00
3.0	Architectural				
	Masonry Works	sqm	331.18	250.00	82,793.75
	Plastering	sqm	662.35	130.00	86,105.50
	Carpentry & Joinery				
	Cabinet Countertops and Hardware	lot	1.00		155,000.00
	Doors including jambs and headers				
	Doors	lot	1.00	30,000.00	45,000.00
	Windows and Glass				
	Windows	lot	1.00	100,000.00	140,000.00
	Bricks and Cladding	sqm	34.00	450.00	45,000.00
	Paintings	sqm	700.00	150.00	105,000.00
	Ceiling Finishes	sqm	150.00	600.00	130,000.00
	Floor Finishes	sqm	130.00	800.00	145,000.00
	Total Architectural				₱933,899.25
4.0	Roofing and Sheetting				
	Total Roofing and Sheetting				₱258,000.00
5.0	Structural				
	Reinforced Concrete Works				
	Column Footing	cu.m	22.50	2,900.00	65,250.00
	Tie Beam	cu.m	23.70	2,900.00	68,730.00
	Slab on Fill	cu.m	35.50	2,900.00	102,950.00
	Steel Works				
	Column: W8x18	pcs	18.00	12500.00	225000.00
	Girder/Beam: W6x9	pcs	31.00	6,500.00	201,500.00
	12mm	pcs	120.00	250.00	30,000.00
	10mm	pcs	340.00	135.00	45,900.00
	Roof Framing Works and Accessories	pck	1.00	145,000.00	145,000.00
	Total Structural				₱884,330.00
6.0	Plumbing				
	4" dia x 10' PVC Pipe	pcs.	63.00	520.00	32,760.00
	2" dia x 10' PVC Pipe	pcs.	75.00	320.00	24,000.00
	1/2" dia x 13' PPR Pipe	pcs.	180.00	130.00	23,400.00
	Teflon Tape	roll	35.00	10.00	350.00

Project : Proposed Construction of One-Storey Residential Building

Location :

Owner :

PVC Cement; 150 cc	can	40.00	165.00	6,600.00
*NH 16" x 24" S.S. Kitchen Sink	set	2.00	600.00	1,200.00
1-faucet comp. w/ fittings				
Water Closet	set	2.00	9,000.00	18,000.00
complete w/ fittings				
*Lavatory - Wt (Sarah)	set	2.00	2,500.00	5,000.00
complete w/ fittings				
CP Shower Valve (complete set)	sets	2.00	3,000.00	6,000.00
CP Shower Head (complete set)	sets	2.00	1,900.00	3,800.00
Hose Bibb Faucet	sets	5.00	350.00	1,750.00
4" x 4" Floor Strainer	pcs.	25.00	150.00	3,750.00
Gate Valve	pcs.	4.00	350.00	1,400.00
Check Valve	pcs.	4.00	350.00	1,400.00
Total Plumbing				₱129,410.00
7.0 Electrical				
Service Entrance Pole				
Gravel G1	cu m	2.00	1,000.00	2,000.00
Sand	cu m	3.00	800.00	2,400.00
Cement	bags	2.00	230.00	460.00
10mm dia. X 6m reinforcement bars	pcs.	3.00	135.00	405.00
12mm dia. X 6m reinforcement bars	pcs.	5.00	205.00	1,025.00
Entrance Cap	set	1.00	550.00	550.00
20mm dia. G.I. Conduit Pipe	m	1.00	185.00	185.00
10mm dia. Copper grounding rod	m	1.00	200.00	200.00
Panel and Breaker				
Panel Box	unit	4.00	750.00	3,000.00
100A Circuit Breaker 2PH	pc	1.00	1,500.00	1,500.00
60A Circuit Breaker 2PH	pc	4.00	450.00	1,800.00
30A Circuit Breaker 2PH	pcs.	10.00	450.00	4,500.00
20A Circuit Breaker 2PH	pcs.	22.00	450.00	9,900.00
Boxes and Conduits				
Utility Box 2"x4"	pcs.	90.00	30.00	2,700.00
Junction Box 4"	pcs.	30.00	30.00	900.00
20mm dia. PVC Conduit Pipe	pcs.	70.00	50.00	3,500.00
Wires and Accessories				
5.5mm2 THHN Wire #10	1m	500.00	36.00	18,000.00
3.5mm2 THHN Wire #12	1m	500.00	35.00	17,500.00
2.0mm2 THHN Wire #14		750.00	27.00	20,250.00
8.0mm2 THHN Wire #8	1m	80.00	58.00	4,640.00
Electrical Tape	rolls	10.00	15.00	150.00
Air Conditioning Outlet	pcs.	3.00	125.00	375.00
Convenience Outlet	pcs.	51.00	55.00	2,805.00

Project : Proposed Construction of One-Storey Residential Building
Location :
Owner :

Convenience Outlet (weatherproof)	pcs.	2.00	75.00	150.00
CO Plate Cover	pcs.	53.00	35.00	1,855.00
Single Pole Switch	pcs.	10.00	45.00	450.00
Two-Gang Switch	pcs.	15.00	95.00	1,425.00
Three-Gang Switch	pcs.	10.00	110.00	1,100.00
1-Gang Plate Cover	pcs.	10.00	25.00	250.00
2-Gang Plate Cover	pcs.	15.00	25.00	375.00
3-Gang Plate Cover	pcs.	10.00	25.00	250.00
Lighting Fixtures				
50W PL Lamps	sets	50.00	150.00	7,500.00
Receptacles				
Telephone Outlet	sets	3.00	160.00	480.00
LAN Outlet	sets	3.00	160.00	480.00
Catv Outlet	sets	3.00	150.00	450.00
Total Electrical				₱113,510.00

Project : Proposed Construction of One-Storey Residential Building
Location :
Owner :

Item	Description	Amount
1.0	Permits	-
2.0	Site Works	₱215,000.00
Sub-total item 1&2		₱215,000.00
3.0	Architectural	₱933,899.25
4.0	Roofings and Sheeting	₱258,000.00
5.0	Structural	₱884,330.00
6.0	Plumbing	₱129,410.00
7.0	Electrical	₱113,510.00
Total Material Cost		₱2,534,149.25
Labor Cost		₱1,013,659.70
Direct Construction Cost		₱3,547,808.95
TOTAL PROJECT COST		₱3,547,808.95